

---

---

---

---

---

---

**B0001561**

***ADDENDUM # 1***

---

**FROM:** *Kim Sowell*

Campus Box 12

Ph: 316-978-3784

Fax: 316-978-3528

---

**TO:** All Bidders

**DATE:** 9/7/2018

**CLOSING DATE AND TIME:** 9/20/2018 @ 2:00 PM

**SUBJECT:** B0001561 Addendum – Door Replacement for Strategic Communications

**ADDITIONS TO BID SPECIFICATIONS:**

- See attachments for addendum details.
- Attached is the pre-bid sign in sheet.

**NO. OF PAGES (including cover sheet): 4**

**Bid Responses must be mailed or hand delivered (faxed and emailed responses are not allowed) to WSU Office of Purchasing prior to the bid closing date and time!**

**Wichita State University  
Office of Purchasing**

Kim Sowell

1845 Fairmount, Campus Box 12

Morrison Hall, Room 021

Wichita, KS 67260-0012

Phone: 316-978-3784 and Fax: 316-978-3528



## **ADDENDUM No.1**

September 10, 2018

### **RE: OFPM-DCC PROJECT #A-013600**

Door Replacement – Office of  
Strategic Communications  
Morrison Hall 1845 Fairmount Street  
Wichita, Ks. 67260-0047

The original Project Manual and Drawings, dated 7/27/2018, for the Project noted above, are amended as indicated on this **Addendum No. 1**. Information provided in this Addendum shall be considered as a portion of the Contract Documents for the referenced Project and the contained information shall supersede all prior documentation.

Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

### **CHANGES TO SPECIFICATIONS**

#### **ADD 1-1**      **Section 087100 “Door Hardware”**

##### 1.6 Quality Assurance, C. Source Limitations:

Obtain each type of door hardware from a single manufacture.

##### 2. Obtain pricing for door access control from the following vendors.

Change from: **Dore Electric**  
**3636 North Topeka**  
**Wichita, Kansas 67219**

To: **CBG Services**  
**151 N. Hydraulic Ave.**  
**Wichita, Ks. 67214**  
**Attention: Chad Dore - (316) 641-3887**

### **CHANGES TO DRAWINGS**

#### **ADD 1-2**      **Drawing Sheet A-100**

The “Door Type Schedule” shows the entry access control key pad located on the wall left of the door side lite. This location is incorrect and should be moved to a new location between the door and side lite, on the wood mullion shown in detail 3/A-100.

## **GENERAL CLARIFICATIONS**

### **ADD 1-3**

Currently at the door sill there's a brass door threshold that makes a transition between the existing terrazzo flooring and the existing carpeting in Strategic Communications. This threshold is to be removed and replaced with a rubber transition strip – "Johnsnite" CTA-XX-J ¼" material to subfloor.

