
B0001688

ADDENDUM # 2

FROM: *Kim Sowell*

Campus Box 12

Ph: 316-978-3784

Fax: 316-978-3528

TO: All Bidders

DATE: 03/17/2021

CLOSING DATE AND TIME: 03/23/2021 @ 2:00 PM

SUBJECT: B0001688 Addendum – Lindquist Hall Electrical Distribution Replacement and Restroom Remodel

CLARIFICATIONS AND ADDITIONS TO BID:

- See attachments for addendum details.

NO. OF PAGES (including cover sheet): 4

Bid Responses must be emailed to kim.sowell@wichita.edu prior to the bid closing date and time! Hand delivered or mailed responses are not allowed to WSU Office of Purchasing.

Wichita State University
Office of Purchasing
Kim Sowell
1845 Fairmount, Campus Box 12
Jardine Hall, Room 201
Wichita, KS 67260-0012
Phone: 316-978-3784

STATE OF KANSAS
CONSTRUCTION PROJECT NO. A-014205

ADDENDUM 2

March 17, 2021

ISSUED BY:

Wichita State University
1845 Fairmount Street
Wichita, Kansas 67260-0047

GLMV Architecture
1525 E. Douglas
Wichita, Kansas 67211
Contact: Meredith Hampton
Phone Number: 316-265-9367
E-Mail: Meredith.hampton@glmv.com

ISSUED FOR ARCHITECT/ENGINEER
NOTICE ALL BIDDERS FOR THE:

Wichita State University
WSU Lindquist Hall Electrical Distribution Replacement and Restroom Remodel
Wichita, Kansas

You are instructed to read and to note the following described changes, corrections, clarifications, omissions, deletions, additions, approvals and statements pertinent to the Contract Bid and Construction Documents.

The Addendum 2 is a part of the Contract Bid and Construction Documents and shall govern in the performance of the Work.

Specifications

Article 2-1, Specification Section 015000 – TEMPORARY FACILITIES AND CONTROLS

- A. Question: Is there an elevator that can be used for material distribution?
- B. Clarification: The elevator is available for use of material distribution. Please ensure sides, floors and all surfaces of elevator are protected adequately and that door tracks remain free of drywall or any other debris. The maximum capacity of the elevator shall not be exceeded.

Article 2-2, Specification Section 0015000 – TEMPORARY FACILITIES AND CONTROLS

- A. Question: Are dust barriers needed on this project?
- B. Clarification: Dust barriers shall be provided. Reference Specification Section 015000, paragraph 3.3,B.,1.

Article 2-3, Clarification

- A. Question: On the finish schedule it calls out ACT Ceiling in the vestibules. Is that what is currently in those locations?
- B. Clarification: Correct. ACT is currently in those vestibules. The Contractor shall replace the existing ceiling with new 2x2 tile and new grid as specified.

Article 2-4, Clarification

- A. Question: What Species of door is needed to match existing?
- B. Clarification: Field verification will be needed to approve door stain color and species. Sample shall be approved by Architect/Owner before order/fabrication of new doors.

Article 2-5, Clarification

- A. Substitution request for Stanley Magic Access Door Operators has not been accepted due to compliance with Owner standards.

Article 2-6, Product Substitutions

- A. Subject to compliance with requirements, add the following to the list of acceptable manufacturers for the following Specification Section:
 - 1. Section 081113 – Hollow Metal Frames: Add paragraph 2.1,A.,4. as follows:
 - a. Mesker Frame Components.

Article 2-7, Clarification

- A. Question: In the A-501 Finish Legend PWT1 calls for Daltile Matchpoint, P127 Ivory White Unpolished. After getting pricing from Daltile, there unpolished is Daltile Matchpoint, P125 Pure White Unpolished. Can you verify that this Daltile Matchpoint, P125 Pure White Unpolished is the product you want.
- B. Clarification: Correct. The unpolished tile color shall be “Pure White P125 Unpolished.”

Article 2-8, Clarification

- A. Question: The American Olean Germain 6x24 & 1x2 Mosaic has been discontinued by the vendor in January of 2020 and they do not have any stock at the mill. So do you want to just leave it as is and budget the price of the material before it got discontinued, if not what material or budget you want me to put for this discontinued material?
- B. Clarification: Please install American Olean St Germain 12x24 the entirety of the floor. The installation shall be brick offset on the 12-inch side of the tile.

Article 2-9, Clarification

- A. Question: In A-501 Finishes Schedule it calls for TR1 (Dilex-AHK) in the 436, 546, 646 Vestibules, there is no wall tile in the vestibules. Do we still want Dilex-AHK there?
- B. Clarification: No TR1 transition strip is required in this area.

Article 2-10, Clarification

- A. Question: Does the masonry brick on the columns in the restrooms remain or are we tiling the columns, can you verify what finish you want there?
- B. Clarification: The masonry brick shall remain as the finish surface for those existing walls.

Drawings (Does Not Apply)

END OF ADDENDUM 2